

PROVINCE OF BRITISH COLUMBIA
MINISTRY OF ENVIRONMENT
WATER MANAGEMENT DIVISION

A HYDROGEOLOGIC
INVENTORY AND RECONNAISSANCE
OF
KEATS ISLAND

D. Johanson, B.Sc.
Groundwater Technician
Groundwater Section
Hydrology Branch
Water Management Division

January 1993

TABLE OF CONTENTS

	<u>Page</u>
TABLE OF CONTENTS	ii
LIST OF FIGURES	iii
LIST OF TABLES	iii
LIST OF APPENDICES	iii
1. INTRODUCTION	1
2. PHYSIOGRAPHY	1
3. BEDROCK GEOLOGY	2
4. SURFICIAL GEOLOGY	2
5. HYDROGEOLOGY	3
6. HYDROCHEMISTRY	3
7. SUMMARY	5
8. REFERENCES	5

LIST OF FIGURES

	<u>Page</u>
FIGURE 1 Location Map	6
FIGURE 2 Mosaic prepared from airphoto coverage of Island	7
FIGURE 3 Keats Island bedrock geology	8
FIGURE 4 Cross-section A - A', Keats Island	9

LIST OF TABLES

TABLE 1	Data summary of wells	10
---------	-----------------------------	----

LIST OF APPENDICES

APPENDIX A	Detailed data report	11
APPENDIX B	Detailed water rights report	30

A HYDROGEOLOGIC INVENTORY AND RECONNAISSANCE OF KEATS ISLAND

INTRODUCTION

Upon receipt of a request from the Sunshine Coast Regional District the Groundwater Section of the Water Management Division undertook a groundwater inventory and reconnaissance of Keats Island.

The Sunshine Coast Regional District is investigating the feasibility of improving water supply on the Island. Part of their investigation involves groundwater and wells. However, no water well data was available in the Groundwater Section Data Base for this Island.

In early October, 1992, the author spent two days on Keats Island. During this time a well inventory was carried out, five wells were sampled for chemical analysis, and a beginning made on a hydrogeological investigation of the Island.

On completion, the Groundwater Section's Data Base was updated with the new water well record and chemistry information obtained, and four new 1 to 5,000 Water Well Location Maps, conforming to the British Columbia Geographical System (BCGS), were prepared for the Island.

This preliminary hydrogeologic report was prepared to present some of the data and to give a few comments on the findings.

PHYSIOGRAPHY

Keats Island has a land area of approximately 600 hectares (1500 acres), primarily made up of sloping terrain rising to a central ridge with summits of around 200 metres (650 feet). It is a rugged island with rock dominated topography which is characterized by frequent bedrock outcrops or shallow overburden over bedrock. The shoreline consists of rock bluffs, separated by beaches of sand or gravel at several points on all sides of the island (Keats Island Community Plan, 1975). Figure 1 shows the location of Keats Island and illustrates the topography.

There are no lakes or major streams on the island, however, a few minor creeks with intermittent flow are present and water rights have been obtained on some of these.

The Island's forests are extensive, mostly coniferous, and are home to a considerable deer and other small animal life population. Figure 2 is a mosaic, prepared from airphoto coverage of the Island.

BEDROCK GEOLOGY

Metamorphosed volcanic and lesser interbedded sedimentary rocks of the Bowen Island Group, along with Coast Plutonic granitic rocks at the east and west ends of the Island, comprise the bedrock of Keats Island. A comprehensive description of these rocks can be found in Roddick, J. A. (1965), "Vancouver North, Coquitlam, and Pitt Lake Map Areas, British Columbia" (G.S.C. Memoir 335). Figure 3 shows Keats Island bedrock geology with generalized strike and dip for bedding and glacial striations (from Armstrong, 1954).

SURFICIAL GEOLOGY

The occurrence of bedrock over much of the island suggests the surficial materials are not very thick. Water well records confirm this. However, two drill logs are reported to penetrate over sixty feet of mainly till before encountering bedrock. No drill records were obtained for the interior valleys and possibly there are isolated deeper pockets of overburden in these areas.

HYDROGEOLOGY

Four well location maps were prepared and are located in the pocket of this report (92G.033.4.3, 92G.033.4.4, 92G.043.2.1 and 92G.043.2.2). Table 1 is a data summary of the sixteen (16) wells located during the field work (6 dug and 10 drilled). Appendix A is a detailed data report for each of these wells. Appendix B is a detailed water rights report for springs and creeks licensed on the Island and three (3) fifty percent reduced water rights maps with location data are enclosed in the pocket (92G.033.4.3, 92G.033.4.4, and 92G.043.2.1).

The predominant source of recharge to groundwater is precipitation, and its hydraulic behaviour is governed by topography, distribution of bedrock and surficial deposits, climate and vegetation. Precipitation replenishes the soil moisture and eventually reaches the water table to replenish the groundwater aquifers. On Keats Island this recharge occurs mainly during the winter months, when precipitation is high and the vegetation is dormant.

A number of dug wells have been completed in the surficial deposits of the Island. They often appear to be adequate for domestic use if precaution is taken with use during late summer. However, where large numbers of people draw on them, which occurs with the three Eastbourne community wells in the summer months, they are not adequate. It was reported that the three Eastbourne dug wells are depleted on weekends in the late summer and it takes a number of the week days for the water level to recover. The owner of dug well 92G.033.4.4.3 #9 reported the water level in his well rose 3 feet overnight after a recent September rainfall, and demonstrates how quickly precipitation recharges this aquifer.

The ability to develop screened wells in the overburden depends on finding saturated permeable materials (ie: sand and gravels). However, the occurrence of bedrock over much of the Island and the drilling to date indicates the surficial material is not very thick. The interior valleys may have some potential.

All drilled wells on the Island are completed in the bedrock and produce groundwater from fractures. The productivity depends on the size and frequency of the fracture openings encountered. The depth of these wells vary from 80 to 407 feet and yield is reported as varying from 35 to 1.0 gpm. However, a 1988 groundwater report by Piteau Associates of West Vancouver, for the Keats Camp water supply notes the 35 gpm well (mentioned above) supplied the Camp for years but in the spring of 1987 the well was incapable of meeting the water demand and rationing was necessary. They estimated the average summer water usage at 10.5 igpm and recommended another well be drilled to make up the camp requirement (Holmes, 1988).

At Eastbourne, a water shortage occurs in the summer. A cross-section A - A' (Figure 4) was drawn for this area. It's location is shown on well location maps 92G.033.4.3 and 92G.033.4.4. It shows bedrock wells with reported yields of 10 and 11 gpm near the east end of the section. This appears to be an area where further groundwater exploration may prove worthwhile for larger supplies. However, water quality and pumptesting should be carried out to confirm the true capacity and quality of the bedrock aquifer. Upstream of Bonner Creek, where it crosses the section line may be an area of overburden potential.

HYDROCHEMISTRY

Groundwater on Keats Island originates from precipitation which infiltrates the soils and rocks and eventually returns to the surface at natural or man-made discharge points. From the point of recharge to the point of discharge the chemical quality of groundwater changes by increasing in total dissolved and suspended solids and by the relative proportions of these constituents.

(4)

During the two days of field work five water samples were collected for analysis in the evening using a Beckman Solu-Bridge and a field Hach kit (model AL-94). Two laboratory analyses were acquired separately.

The results are summarized as follows:

- | | |
|-------------------------|--------------------------------------|
| 1) pH | varied from 6.6 to 7.92 |
| 2) Hardness | varied from 51 to 187 ppm |
| 3) Specific Conductance | varied from 110 to 400 micro/mhos/cm |
| 4) NaCl | less than 37.5 ppm |
| 5) Total Alkalinity | varied from 68 to 170 ppm |

All above parameters tested show values acceptable for drinking water. A laboratory analysis for well 92G.033.4.4.3 #1 showed acceptable water, except for manganese which tested as 0.22 mg/liter. The proposed aesthetic objective for this parameter is less than or equal to 0.05 mg/L (Guidelines for Canadian Drinking Water Quality, 1989). At values exceeding 0.05 mg/L it may stain both plumbing fixtures and clothes being washed.

The laboratory analyses are included with the detailed data report in Appendix A.

SUMMARY

- 1) Dug well owners report a significant decrease in yield during the late summer.
- 2) Individual domestic water supplies can probably be obtained from most wells drilled on Keats Island, if drilled to sufficient depth.
- 3) Small community systems may obtain a supply exceeding 10 gpm from favourably located bedrock wells.
- 4) Sites for screened wells in sand and gravel are not very favourable due to the shallow overburden. However, there may be potential in the valley bottoms where the irregular bedrock topography may have channelled glacial melt waters and left permeable materials.
- 5) All water quality parameters tested, in samples collected, were below the maximum allowable concentrations as given in the "Guidelines for Canadian Drinking Water Quality, 1989", except for well 92G.033.4.4.3 #1 which had an elevated concentration of manganese (0.22 mg/L).

REFERENCES

- Armstrong, J.E. 1954. Preliminary Map, Vancouver North, British Columbia Geological Survey of Canada, Paper 53-28.
- Health and Welfare Canada. 1989. Guidelines for Canadian Drinking Water Quality 1989, Health and Welfare Canada, Ottawa.
- Holmes, A.T. 1988. Well for Keats Camp Water Supply. Piteau Associates. West Vancouver, British Columbia. Unpublished Report.
- Keats Island Community Plan, 1975. Regional District of Sunshine Coast, By-Law No. 107, Sechelt, British Columbia.
- Roddick, J. A. 1965. Vancouver North, Coquitlam, Pitt Lake Map-Areas, British Columbia. Geological Survey of Canada, Memoir 335.

D. Johanson, B.Sc.
Groundwater Technician
Groundwater Section
Hydrology Branch
Water Management Division






Fig 1 : KEATS ISLAND



(7)

Figure 2 : Airphoto Mosaic of Keats Island



LEGEND




Fig 3 : KEATS ISLAND GEOLOGY

Geology by J. E. Armstrong, 1948-51




Figure 4 : Cross-Section A - A', Keats Island

LEGEND

Static Water Level..... swl
 Horizontal Scale: 1 to 5,000
 Vertical Scale: as shown
 Surficial Deposits.....sd

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Data Summary - with Legal Descriptions

BCGS Map Area	Well No.	Lot No.	Plan No.	Blk No.	TP	SC	RG	D.L.	L.D.	Owner's Name	Date Constructed (day)	Well Depth (ft.)	Well Diam. (in.)	Drill Contr No.	Const. Method	Well Yield	Yld. Unt.	Depth to Water (ft.)	Depth to Bedrk (ft.)	Aquif Litho	Screen Interval (ft.)	G.W. Rpt	Chem Lab	Chem Fld	Chem Site No.
092G.033.4.3.3	001							696	37	KEATS CAMP(BABTIST)	01-01-68	160.0	6.0	265	DRI	35.0	GPM		40	BED		Y		Y	
092G.033.4.3.4	001	7	6646					1467	37	DAVID BENTALL	01-01-67	80.0	6.0	120	DRI	3.0	GPM		0	BED			Y		
092G.033.4.3.4	002		18682	23				1593	37	CHUCK PEARSON	06-05-92	185.0	6.0	101	DRI	4.0	GPM	56	18	BED					
092G.033.4.4.3	001	11	10378					1595	37	D. PUDDIFANT	20-08-91	145.0	6.0	101	DRI	11.0	GPM		2	BED			Y		
092G.033.4.4.3	002	6	10378	16				1595	37	SOREN NILSSON	14-05-92	165.0	6.0	101	DRI	10.0	GPM	46	9	BED					
092G.033.4.4.3	003	2	10378	19				1595	37	EASTBOURNE COMMUNITY	01-01-50	20.0	84.0	UNK	DUG				UNK	UNC					
092G.033.4.4.3	004		18682	30				1594	37	CARL WALTERS	09-05-92	265.0	6.0	101	DRI	2.0	GPM	68	1	BED				Y	
092G.033.4.4.3	005		18682	30				1594	37	CARL WALTERS		15.0	24.0	UNK	DUG				UNK	UNC				Y	
092G.033.4.4.3	006							1595	37	EASTBOURNE COMMUNITY		20.0	60.0	UNK	DUG			8	UNK	UNC					
092G.033.4.4.3	007		18682	27				1593	37	EASTBOURNE COMMUNITY		20.0	120.0	UNK	DUG			10	UNK	UNC					
092G.033.4.4.3	008	A	2668					1593	37	MR. GEORGE KONING		11.0	0.0	UNK	DUG				UNK	UNC					
092G.033.4.4.3	009		18682	27				1593	37	GEORGE KONING		11.0	144.0	UNK	DUG			6	UNK	UNC					
092G.043.2.1.2	001							1468	37	ENV.,LANDS & PARKS		235.0	6.0	081	DRI	20.0	GPM	22	24	BED				Y	
092G.043.2.1.2	002							1469	37	BARNABUS FAMILY MIN.	07-07-89	407.0	6.0	032	DRI	3.0	GPM	30	66	BED					
092G.043.2.2.1	001		18682	41				1594	37	LEX HANSON(JORDANS)	15-08-91	245.0	6.0	101	DRI	5.0	GPM		2	BED				Y	
092G.043.2.2.1	002		18682	40				1594	37	RICHARD HAMMOND	17-09-83	200.0	6.0	101	DRI	1.0	GPM	45	59	BED					

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information. This information should not be used as a basis for making financial or any other commitments.

Table 1 : Data Summary of Wells

APPENDIX A

Detailed Data Report

27/01/93

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

Page 12

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.3.3 - 001

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 696 Township : Meridian :
Plan No. : Section : Block :
Lot No. : Range : Quarter :

Owner Name : KEATS CAMP(BABTIST) MOE OBS WELL : 000
Address(Well):
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: 265 - FRIESEN DRILLING
Certificate Number :
Constr. Date (ymd): 68 01 01 Constr. Method: Drilled

Comment: ORIGINALLY RATED AT 35GPM BUT 1988 REPORT BELIEVES IT PRODUCES APPROX, 10GPM
SUPPLY APPROX. 80 CABINS, FLOWS DURING WINTER MONTHS. INADEQUATE IN LATE SUMMER.

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 6.0 inch
Total Well Depth: 160.0 feet
Depth to Water : feet
Artesian Flow : 0.0
Est. Well Yield : 35.0 GPM
Depth to Bedrock: 40 feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Bedrock
Well Use : Domestic
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: yes Chemistry (Field) : yes
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0 -	40.0	stoney clay & till?			
40.0 -	160.0	bedrock (fractured at 100ft.)			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.3.4 - 001

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1467 Township : Meridian :
Plan No. : 6646 Section : Block :
Lot No. : 7 Range : Quarter :

Owner Name : DAVID BENTALL MOE OBS WELL : 000
Address(Well):
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: 120 - RURAL WELL DRILLERS
Certificate Number :
Constr. Date (ymd): 67 01 01 Constr. Method: Drilled

Comment: WATER ENTERS WELL PRIMARILY FROM FRACTURE AT 70 FT.

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 6.0 inch
Total Well Depth: 80.0 feet
Depth to Water : feet
Artesian Flow : 0.0
Est. Well Yield : 3.0 GPM
Depth to Bedrock: 0 feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Bedrock
Well Use : Domestic
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) : yes
Groundwater Report: Chemistry (Field) :
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0	- 80.0	bedrock (not very hard)			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.3.4 - 002

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1593 Township : Meridian :
Plan No. : 18682 Section : Block : 23
Lot No. : Range : Quarter :

Owner Name : CHUCK PEARSON MOE OBS WELL : 000
Address(Well):
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: 101 - NOR-WEST WELL DRILLING
Certificate Number :
Constr. Date (ymd): 92 05 06 Constr. Method: Drilled

Comment: DARK FINE GRAINED BEDROCK OUTCROPS NEAR WELLSITE

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 6.0 inch
Total Well Depth: 185.0 feet
Depth to Water : 56 feet
Artesian Flow : 0.0
Est. Well Yield : 4.0 GPM
Depth to Bedrock: 18 feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Bedrock
Well Use : Domestic
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) :
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0	5.0	fill			
5.0	12.0	sand & gravel			
12.0	18.0	gravel & cobbles			
18.0	70.0	green granite (some fractures)			
70.0	82.0	light green granite(some fractures)			
0.0	0.0	1 gpm at 70-82 ft			
82.0	106.0	black granite			
106.0	124.0	black granite & lense of quartz			
0.0	0.0	1 gpm at 106-124			
124.0	156.0	green granite			
156.0	169.0	fractured green granite (2 gpm)			
169.0	185.0	black granite			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.4.3 - 001

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1595 Township : Meridian :
Plan No. : 10378 Section : Block :
Lot No. : 11 Range : Quarter :

Owner Name : D. PUDDIFANT MOE OBS WELL : 000
Address (Well) :
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: 101 - NOR-WEST WELL DRILLING
Certificate Number :
Constr. Date (ymd): 91 08 20 Constr. Method: Drilled

Comment: LIGHT GREEN, FINE GRAINED BEDROCK OUTCROPS AT ROAD, 20' FROM WELLSITE.
SULPHURY SMELL IN SUMMER & INSTALLED A CHARCOAL FILTER.TDS 197,HARDNESS 131.

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 6.0 inch
Total Well Depth: 145.0 feet
Depth to Water : feet
Artesian Flow : 0.0
Est. Well Yield : 11.0 GPM
Depth to Bedrock: 2 feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Bedrock
Well Use : Domestic
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) : yes
Groundwater Report: Chemistry (Field) :
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0 -	2.0	stoney soil & boulders			
2.0 -	5.0	hard green granite			
5.0 -	11.0	hard black granite			
11.0 -	32.0	hard green granite (some fractures)			
32.0 -	47.0	hard purple granite (some fractures)			
47.0 -	49.0	soft grey granite			
49.0 -	62.0	hard black granite (some fractures)			
62.0 -	72.0	hard purple granite (fractures)			
72.0 -	120.0	hard brown shale & layers of black			
0.0 -	0.0	shale (.5gpm @ 75'-85' & .5gpm @ 95-105')			
120.0 -	140.0	hard green granite, some fractures			
140.0 -	145.0	hard green granite, some quartz and			
0.0 -	0.0	fractures (10 gpm.)			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

66-11 BCR 16 D 155
 Jan 1955 ROK 1111

REPORT ON: Results of Testing

CANTEST

CanTest Ltd

REPORTED TO: Mr. Jeff Bird
 Westpoint Sales Inc.
 3940 Grant Street
 Burnaby, BC V5C 3N3

Professional
 Analytical
 Services

FILE NO: 5653-J

Suite 200
 1523 West 3rd Ave
 Vancouver, BC
 V6J 1J8

DATE: August 25, 1992

Fax: 604 731 2386

Tel: 604 734 7278

We have tested the sample of water submitted by you and report as follows:

SAMPLE IDENTIFICATION:

PROJECT NAME: Water Quality
 DATE SAMPLED: Not specified
 DATE SUBMITTED: July 24, 1992
 TYPE OF CONTAINER: Plastic

RESULTS OF TESTING:

CANTEST ID #: 5653-J
 CLIENT ID #: KEATS WATER

pH (pH units)	7.92
Total Dissolved Solids	197.
Hardness (as CaCO ₃)	131.
Sulphide	<0.05
Total Iron Fe	0.19
Total Manganese Mn	0.22

< = Less than


All results expressed in milligrams per litre unless otherwise stated.

METHODS OF TESTING:

The analyses were carried out in accordance with procedures described in "Laboratory Manual for the Chemical Analysis of Water, Wastewater, Sediments and Biological Materials (2nd Edition)", published by the Government of B.C., Ministry of Environment, Water Resources Services, 1976 and "Standard Methods for the Examination of Water and Wastewater" 17th Edition, 1989 and 16th Edition, 1985, published by the American Public Health Association.

The metals were determined using Inductively Coupled Plasma Spectrographic Analysis, direct or graphite furnace atomic absorption spectrophotometry.

CANTEST LTD.


 (P) Richard S. Jomitz, A.Sc.T.
 Supervisor
 Inorganic Testing

RSJ:jr
 C:\WATERLAB\BIRD5653

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.4.3 - 002

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1595 Township : Meridian :
Plan No. : 10378 Section : Block : 16
Lot No. : 6 Range : Quarter :

Owner Name : SOREN NILSSON MOE OBS WELL : 000
Address(Well):
Area/Town
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: 101 - NOR-WEST WELL DRILLING
Certificate Number :
Constr. Date (ymd): 92 05 14 Constr. Method: Drilled

Comment: GREYISH WHITE, LAYERED , FINE GRAINED BEDROCK OUTCROPS IN IMMEDIATE AREA

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 6.0 inch
Total Well Depth: 165.0 feet
Depth to Water : 46 feet
Artesian Flow : 0.0
Est. Well Yield : 10.0 GPM
Depth to Bedrock: 9 feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Bedrock
Well Use : Domestic
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) :
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0	2.0	stone top soil			
2.0	9.0	silty sand, gravel & cobbles			
9.0	34.0	grey & green granite			
34.0	78.0	purple & grey granite			
78.0	96.0	brown & light green granite, fractures			
0.0	0.0	1 gpm			
96.0	134.0	light green granite			
134.0	156.0	green & brown granite (fractures 9 gpm)			
156.0	165.0	green granite			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.4.3 - 003

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1595 Township : Meridian :
Plan No. : 10378 Section : Block : 19
Lot No. : 2 Range : Quarter :

Owner Name : EASTBOURNE COMMUNITY MOE OBS WELL : 000
Address(Well):
Area/Town : EASTBOURNE
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: UNK - Unknown
Certificate Number :
Constr. Date (ymd): 50 01 01 Constr. Method: Dug

Comment: REPORTED: 7 FT.SQUARE CEDAR CRIBBED FOR 1ST 4 FT THEN OPEN HOLE GOOD QUALITY,

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 84.0 inch
Total Well Depth: 20.0 feet
Depth to Water : feet
Artesian Flow : 0.0
Est. Well Yield : 0.0
Depth to Bedrock: UNK feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0 0
Aquifer Litho. : Unconsolidated
Well Use : Commercial and Industrial
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) :
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0 -	20.0	till, water enters in grey gravelly			
0.0 -	0.0	seams in till			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.4.3 - 004

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1594 Township : Meridian :
Plan No. : 18682 Section : Block : 30
Lot No. : Range : Quarter :

Owner Name : CARL WALTERS MOE OBS WELL : 000
Address(Well):
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: 101 - NOR-WEST WELL DRILLING
Certificate Number :
Constr. Date (ymd): 92 05 09 Constr. Method: Drilled

Comment: LIGHT PURPLISH & GREENISH, FINE GRAINED BEDROCK OUTCROPS IN AREA
SPEC. CONDUCT. 370, NACL <25PPM, HARDNESS 187 PPM.

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 6.0 inch
Total Well Depth: 265.0 feet
Depth to Water : 68 feet
Artesian Flow : 0.0
Est. Well Yield : 2.0 GPM
Depth to Bedrock: 1 feet
Screen (from): 0 feet (to): 0 0 feet
Slot Size : 0 0
Aquifer Litho. : Bedrock
Well Use : Domestic
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) : yes
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0	1.0	top soil			
1.0	28.0	purple & grey granite			
28.0	46.0	fractured purple & grey green granite			
46.0	78.0	grey & green granite			
78.0	96.0	fractured grey & brown granite (1gpm)			
96.0	110.0	grey & brown granite			
110.0	140.0	green granite			
140.0	150.0	grey, brown granite (fractures .5 gpm)			
150.0	195.0	green granite			
195.0	205.0	black, grey & green granite, some			
0.0	0.0	quartz lenses			
205.0	240.0	layers of grey, black & brown granite			
240.0	255.0	fractured grey granite (.5 gpm)			
255.0	265.0	green granite			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.4.3 - 005

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1594 Township : Meridian :
Plan No. : 18682 Section : Block : 30
Lot No. : Range : Quarter :

Owner Name : CARL WALTERS MOE OBS WELL : 000
Address(Well):
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: UNK - Unknown

Certificate Number :

Constr. Date (ymd): Constr. Method: Dug

Comment: CORRUGATED GALVANIZED CASING, METALLIC TASTE, GRAVELLY SURFACE MATERIAL AT SITE
HANDPUMP ON WELL, SPEC. COND.110,PH 6.6 FE. 4, NACL <25 PPM, HARDNESS 51 PPM.

FROM TO DRILLER LOG
0.0 - 0.0 gravelly at surface

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 24.0 inch
Total Well Depth: 15.0 feet
Depth to Water : feet
Artesian Flow : 0.0
Est. Well Yield : 0.0
Depth to Bedrock: UNK feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Unconsolidated
Well Use : ABANDONED
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) : yes
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

MATERIAL

DESCRIPTION

COLOR

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

27/01/93

Page 22

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.4.3 - 006

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1595 Township : Meridian :
Plan No. : Section : Block :
Lot No. : Range : Quarter :

Owner Name : EASTBOURNE COMMUNITY MOE OBS WELL : 000
Address(Well):
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: UNK - Unknown
Certificate Number :
Constr. Date (ymd): Constr. Method: Dug

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 60.0 inch
Total Well Depth: 20.0 feet
Depth to Water : 8 feet
Artesian Flow : 0.0
Est. Well Yield : 0.0
Depth to Bedrock: UNK feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0 0
Aquifer Litho. : Unconsolidated
Well Use : Commercial and Industrial
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) :
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

Comment: THIS WELL IS NOT CASED TO THE BOTTOM, BUT WAS OBSERVED TO BE CASED BELOW THE H2O
LEVEL IN WELL.HEAVY USE ON SUMMER WEEKENDS DEPLETES WELL.SYPHON SYSTEM NO PUMP.

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0 -	0.0	fine silty			
0.0 -	0.0	water enters well through grey gravelly			
0.0 -	0.0	seams in till			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.4.3 - 007

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1593 Township : Meridian :
Plan No. : 18682 Section : Block : 27
Lot No. : Range : Quarter :

Owner Name : EASTBOURNE COMMUNITY MOE OBS WELL : 000
Address(Well):
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: UNK - Unknown

Certificate Number :

Constr. Date (ymd): Constr. Method: Dug

Comment: SYPHON SYSTEM. ON SUMMER WEEKENDS WHEN A FEW HUNDRED PEOPLE ARRIVE THE WELL IS
DEPLETED. IT RECOVERS ON THE WEEK DAYS.OPEN HOLE BELOW CRIBBING.IN WOODED AREA.

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 120.0 inch
Total Well Depth: 20.0 feet
Depth to Water : 10 feet
Artesian Flow : 0.0
Est. Well Yield : 0.0
Depth to Bedrock: UNK feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0 0
Aquifer Litho. : Unconsolidated
Well Use : Commercial and Industrial
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) :
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0 -	2.0	gravelly			
2.0 -	20.0	till, water enters well through gravelly			
0.0 -	0.0	grey seams in till			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

Aug-90

ZENON ENVIRONMENTAL INC.
B.C. LABORATORY SERVICES
Report for form 02003186

Page- 124

General Public

ATTN: BENTALL D

Sample 90006571

Site: NOSITE WELL VFT *70'*

From : 90/07/13:0000

To : 90/07/13:0000

Depth Range : 0.0 0.0

Tide :

Sample State: Fresh Water

Sample Comment:

Parameter Description	Result	Units	Analytical Technique
pH	7.3	pH units	Automated pH Meter
Specific Conductance	200	uS/cm	Cond. Meter Siebold
Turbidity	0.1	NTU	Nephel. Single Beam
Alkalinity Total 4.5	91.2	mg/L	Automated Electrometer
Hardness Total	104	mg/L	Calculated Result
Coliform - Total	< 2.0	CFU	Filter-Membrane
Fluoride Dissolved	< 0.10	mg/L	I. S. E.
Boron	< 0.01	mg/L	ICP Analysis
Barium	< 0.01	mg/L	ICP Analysis
Calcium	36.7	mg/L	ICP Analysis
Chromium	< 0.01	mg/L	ICP Analysis
Copper	0.06	mg/L	ICP Analysis
Iron	< 0.01	mg/L	ICP Analysis
Magnesium	2.98	mg/L	ICP Analysis
Manganese	< 0.01	mg/L	ICP Analysis
Lead	0.001	mg/L	HNO3 Dig: HGA Analysis
Zinc	< 0.01	mg/L	ICP Analysis
Nitrogen NO3+NO2 Dis	0.15	mg/L	Auto. Cadmium Reduction
Nitrogen NO3 Diss(N)	0.15	mg/L	Calculated Result
Nitrogen NO2 Diss(N)	< 0.005	mg/L	Auto. Diazotization

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.4.3 - 008

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1593 Township : Meridian :
Plan No. : 2668 Section : Block :
Lot No. : A Range : Quarter :

Owner Name : MR. GEORGE KONING MOE OBS WELL : 000
Address(Well):
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: UNK - Unknown
Certificate Number :
Constr. Date (ymd): Constr. Method: Dug

Comment: SUPPLIES LOG HOUSE ON PARCEL A, REF PLAN 2668 , DUG WITH BACKHOE.

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 0.0 inch
Total Well Depth: 11.0 feet
Depth to Water : feet
Artesian Flow : 0.0
Est. Well Yield : 0.0
Depth to Bedrock: UNK feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Unconsolidated
Well Use : Domestic
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) :
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0 -	2.0	grey gravelly soil			
2.0 -	11.0	till (water enters through grey gravelly			
0.0 -	0.0	seams in till).			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.033.4.4.3 - 009

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1593 Township : Meridian :
Plan No. : 18682 Section : Block : 27
Lot No. : Range : Quarter :

Owner Name : GEORGE KONING MOE OBS WELL : 000
Address(Well):
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - - - - - - -

Drilling Contr. Name: UNK - Unknown
Certificate Number :
Constr. Date (ymd): Constr. Method: Dug

Comment: USE FOR HOUSE AND GARDEN, NEVER RAN DRY BUT ONLY 18" OF WATER IN WELL IN LATE
AUGUST (1992) BUT WITH RECENT RAIN IN SEPT. THE WATER LEVEL ROSE 3 FT. ONE NIGHT

FROM	TO	DRILLER LOG
0.0 -	2.0	grey gravelly soil
2.0 -	11.0	till (water enters through grey
0.0 -	0.0	gravelly seams in till).

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 144.0 inch
Total Well Depth: 11.0 feet
Depth to Water : 6 feet
Artesian Flow : 0.0
Est. Well Yield : 0.0
Depth to Bedrock: UNK feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Unconsolidated
Well Use : Domestic
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) :
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

MATERIAL

DESCRIPTION

COLOR

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

27/01/93

Page 26

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.043.2.1.2 - 001

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1468 Township : Meridian :
Plan No. : Section : Block :
Lot No. : Range : Quarter :

Owner Name : ENV., LANDS & PARKS MOE OBS WELL : 000
Address(Well): PLUMBER COVE PROV. PARK
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - - - - - -

Drilling Contr. Name: 081 - LANGLEY WATER WELLS
Certificate Number :
Constr. Date (ymd): Constr. Method: Drilled

Comment: OCT.92 JUST A HANDPUMP ON WELL, IT IS USED FOR DRINKING WATER. FIELD ANALYSIS :
SPEC. COND. 200 MICROMHOS/CM, PH 6.8, NACL <25 PPM, HARDNESS 68 PPM.

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 6.0 inch
Total Well Depth: 235.0 feet
Depth to Water : 22 feet
Artesian Flow : 0.0
Est. Well Yield : 20.0 GPM
Depth to Bedrock: 24 feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Bedrock
Well Use : Other
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) : yes
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0 -	10.0	till			
10.0 -	23.0	clay with stones			
23.0 -	24.5	silty clay			
24.5 -	235.0	bedrock, fractures @ 115', 207', 222'			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

27/01/93

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

Page 27

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.043.2.1.2 - 002

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1469 Township : Meridian :
Plan No. : Section : Block :
Lot No. : Range : Quarter :

Owner Name : BARNABUS FAMILY MIN. MOE OBS WELL : 000
Address(Well) :
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: 032 - DRILLWELL ENT. / KEN SLADE
Certificate Number :
Constr. Date (ymd): 89 07 07 Constr. Method: Drilled

TECHNICAL DETAILS:

Ground Elevation: 10 feet
Well Diameter : 6.0 inch
Total Well Depth: 407.0 feet
Depth to Water : 30 feet
Artesian Flow : 0.0
Est. Well Yield : 3.0 GPM
Depth to Bedrock: 66 feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Bedrock
Well Use : Domestic
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) :
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

Comment: THIS IS THE "CORKUM FARM", QUALITY STATED AS GOOD AND ADEQUATE SUPPLY

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0	5.0	soil			
5.0	40.0	grey silt with sand layer			
40.0	66.0	till with boulders			
66.0	407.0	shale and sandstone			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.043.2.2.1 - 001

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1594 Township : Meridian :
Plan No. : 18682 Section : Block : 41
Lot No. : Range : Quarter :

Owner Name : LEX HANSON(JORDANS) MOE OBS WELL : 000
Address(Well):
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: 101 - NOR-WEST WELL DRILLING
Certificate Number :
Constr. Date (ymd): 91 08 15 Constr. Method: Drilled

Comment: PLUTONIC BANDED BEDROCK OBSERVED AT SITE,SOME BANDS PINK AND TO 3 FT WIDE.
FIELD TEST:SPEC. COND. 400,PH 7.7(?),NACL <25 PPM HARDNESS 170 PPM.

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 6.0 inch
Total Well Depth: 245.0 feet
Depth to Water : feet
Artesian Flow : 0.0
Est. Well Yield : 5.0 GPM
Depth to Bedrock: 2 feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Bedrock
Well Use : Domestic
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) : yes
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0 -	2.0	fill			
2.0 -	7.0	multi coloured granite(fractured)			
7.0 -	12.0	hard green granite			
12.0 -	22.0	hard green and white granite			
22.0 -	90.0	hard multi coloured granite			
0.0 -	0.0	65-75ft. 1 gpm			
90.0 -	140.0	hard green & white granite			
140.0 -	145.0	pink granite (140-150ft .5 gpm)			
145.0 -	170.0	hard green & white granite			
170.0 -	240.0	fratured green & white granite			
240.0 -	245.0	green & pink granite (fractured)4gpm.			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

Ministry of Environment - Water Management Branch - Groundwater Section
Groundwater Database System
Detailed Data Report

WELL IDENTIFICATION DETAILS:

BCGS MAP AREA - WELL NO.: 092G.043.2.2.1 - 002

Land Dist. : 37 - NEW WESTMINSTER Ind. Res. :
Dist. Lot : 1594 Township : Meridian :
Plan No. : 18682 Section : Block : 40
Lot No. : Range : Quarter :

Owner Name : RICHARD HAMMOND MOE OBS WELL : 000
Address(Well):
Area/Town :
Island Name : KEATS
Permit No. : Loc. Accur. :

UTM : Z- E- N-
Old Coord. : Z-00 X-00 Y-00 TP- SC- RG-
Old Well No. : 000 Old Map No. : 000
Watershed Code: - - - - -

Drilling Contr. Name: 101 - NOR-WEST WELL DRILLING
Certificate Number :
Constr. Date (ymd): 83 09 17 Constr. Method: Drilled

Comment: OCT.92 WELL NOT IN USE

TECHNICAL DETAILS:

Ground Elevation: 0 feet
Well Diameter : 6.0 inch
Total Well Depth: 200.0 feet
Depth to Water : 45 feet
Artesian Flow : 0.0
Est. Well Yield : 1.0 GPM
Depth to Bedrock: 59 feet
Screen (from): 0 feet (to): 0 feet
Slot Size : 0 0
Aquifer Litho. : Bedrock
Well Use : Domestic
Water Utility :

OTHER AVAILABLE INFORMATION:

Pump Test Data : Chemistry (Lab) :
Groundwater Report: Chemistry (Field) :
Sieve Analysis : Chemistry Site No.:
Screen Details :
Other :

FROM	TO	DRILLER LOG	MATERIAL	DESCRIPTION	COLOR
0.0	4.0	stoney clay			
4.0	16.0	hardpan			
16.0	59.0	till & grey clay			
59.0	63.0	cap rock, hard black granite			
63.0	93.0	hard grey granite			
93.0	155.0	grey granite & layers of sandstone			
0.0	0.0	.5 gpm at 130' - 140'			
155.0	200.0	hard grey granite, some cracks			
0.0	0.0	.5 gpm at 160' - 180'			

DISCLAIMER: The Province disclaims all responsibility for the accuracy of this information.
This information should not be used as a basis for making financial or any other commitments.

APPENDIX B
Detailed Water Rights Report

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29
TIME: 11:02
PAGE: 001

Licence Number: C016074 File Number: 0152459
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT Priority Date: 1944/05/08
Process Status: Lic. Status Date: 1991/05/24
Lic. Exp. Date: - Proc Status Date: -
Fee Receipt No: LTO Code & PID:

Appurtenancy:
3.81 AC PARCEL A OF L 1593 GP 1 NWD PLAN 2668

Licensee No. 1 (Client Last Updated: / / By Region:)
Client No: 23111
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Total Licence Demand:
PUC Description Quantity/Units From To Irrigated Area
01A DOM 2,000.000 GD Jan.01 Dec.31 -

Licence Comments:

POD 1:
Map No: WR 92.G.033.4.4 POD: A Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A DOM 2,000.000 G T Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Bonner Creek Gaz/Alias: G

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29
TIME: 11:02
PAGE: 002

Licence Number: C024801
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT
Process Status:
Lic. Exp. Date: -
Fee Receipt No:

File Number: 0221590
Priority Date: 1958/08/11
Lic. Status Date: 1991/05/24
Proc Status Date: -
LTO Code & PID:

Appurtenancy:
L 14 & 15 OF BLK G L 696 KEATS I GP 1 NWD AS SHOWN ON ATTACHED
PLAN

Licensee No. 1 (Client Last Updated: / / By Region:)
Client No: 23154
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Total Licence Demand:					
PUC	Description	Quantity/Units	From	To	Irrigated Area
01A	DOM	500.000 GD	Jan.01	Dec.31	-

Licence Comments:

POD 1:
Map No: WR 92.G.033.4.3 POD: A
PUC Description Quantity/Units Qty Sto From To Rediv: N
01A DOM 500.000 G T Jan.01 Dec.31 Irrigated Area -
POD Comments:
WSC: KEA Source: Resort Spring Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29
TIME: 11:02
PAGE: 003

Licence Number: C024802
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT
Process Status:
Lic. Exp. Date: -
Fee Receipt No:

File Number: 0222697
Priority Date: 1958/10/29
Lic. Status Date: 1991/05/24
Proc Status Date: -
LTO Code & PID:

Appurtenancy:
L 12 & 13 OF BLK G OF L 696 KEATS I GP 1 NWD AS SHOWN ON ATTACHED
PLAN

Licensee No. 1 (Client Last Updated: / /

By Region:)
Client No: 23155
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Total Licence Demand:

PUC	Description	Quantity/Units	From	To	Irrigated Area
01A	DOM	500.000 GD	Jan.01	Dec.31	-

Licence Comments:

POD 1:

Map No: WR 92.G.033.4.3

POD: A

PUC Description

Quantity/Units Qty Sto

From To
Jan.01 Dec.31

Rediv: N
Irrigated Area
-

01A DOM

500.000 G T

POD Comments:

WSC: KEA

Source: Resort Spring

Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29
TIME: 11:02
PAGE: 004

Licence Number: C024804
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT
Process Status:
Lic. Exp. Date: -
Fee Receipt No:

File Number: 0221737
Priority Date: 1958/08/19
Lic. Status Date: 1991/05/24
Proc Status Date: -
LTO Code & PID:

Appurtenancy:
L 18 & 19 OF BLK G OF L 696 KEATS I GP 1 NWD AS SHOWN ON ATTACHED
PLAN

Licensee No. 1 (Client Last Updated: / / By Region:)
Client No: 23156
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Total Licence Demand:

PUC	Description	Quantity/Units	From	To	Irrigated Area
01A	DOM	1,000.000 GD	Jan.01	Dec.31	-

Licence Comments:

POD 1:
Map No: WR 92.G.033.4.3 POD: A Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A DOM 1,000.000 G T Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Resort Spring Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29

TIME: 11:02

PAGE: 005

Licence Number: C024874
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT
Process Status:
Lic. Exp. Date: -
Fee Receipt No:

File Number: 0221550
Priority Date: 1958/08/06
Lic. Status Date: 1991/05/24
Proc Status Date: -
LTO Code & PID:

Appurtenancy:
L 1428 SHELTER ISLETS KEATS I GP 1 NWD

Licensee No. 1 (Client Last Updated: / / By Region:)
Client No: 23157
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Permits Over Crown Land:			Acres	Billed With Lic
PCL No	Code	Description		
04511	06C	OTHER - PIPELINE, ETC	0.250	Y

Total Licence Demand:		Quantity/Units	From	To	Irrigated Area
PUC	Description				
01A	DOM	1,000.000 GD	Jan.01	Dec.31	-

Licence Comments:

POD 1:
Map No: WR 92.G.033.4.3 POD: A Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A DOM 1,000.000 G T Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Resort Spring Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29
TIME: 11:02
PAGE: 006

Licence Number: C025054 File Number: 0224862
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND Priority Date: 1959/04/03
Licence Status: C CURRENT Lic. Status Date: 1991/05/24
Process Status: Proc Status Date: -
Lic. Exp. Date: - LTO Code & PID:
Fee Receipt No:

Appurtenancy:
L 9 OF L X OF L 1468 GP 1 NW1 PLAN 8097

Licensee No. 1 (Client Last Updated: 1992/05/14 By Region: 00)
Client No: 23159
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Total Licence Demand:
PUC Description Quantity/Units From To Irrigated Area
01A IOM 250.000 GD Jan.01 Dec.31 -

Licence Comments:

POD 1:
Map No: WR 92.G.043.2.1 POD: E Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A IOM 250.000 G M Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Alderson Spring Gaz/Alias: A

POD 2:
Map No: WR 92.G.043.2.1 POD: D Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A IOM 250.000 G M Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Brown Spring Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29
TIME: 11:02
PAGE: 007

Licence Number: C025055 File Number: 0226001
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND Priority Date: 1959/04/03
Licence Status: C CURRENT Lic. Status Date: 1991/05/24
Process Status:
Lic. Exp. Date: - Proc Status Date: -
Fee Receipt No: LTO Code & PID:

Appurtenancy:
L 10 OF L X OF L 1468 GP 1 NWD PLAN 8397

Licensee No. 1 (Client Last Updated: / / By Region:)
 Client No: 23160
 Work Phone: -----
 Home Phone: -----
 Receives Bill: Y

Total Licence Demand:
PUC Description Quantity/Units From To Irrigated Area
01A DOM 250.000 GD Jan.01 Dec.31 -

Licence Comments:

POD 1:
Map No: WR 92.G.043.2.1 POD: E Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A DOM 250.000 G M Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Alderson Spring Gaz/Alias: A

POD 2:
Map No: WR 92.G.043.2.1 POD: D Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A DOM 250.000 G M Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Brown Spring Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29

TIME: 11:02

PAGE: 008

Licence Number:	C025057	File Number:	0226003
Dist/Prec:	29C VAN - HOWE SOUND	Priority Date:	1959/04/03
Region:	02 LOWER MAINLAND	Lic. Status Date:	1991/05/24
Licence Status:	C CURRENT	Proc Status Date:	-
Process Status:		LTD Code & PID:	
Lic. Exp. Date:	-		
Fee Receipt No:			

Appurtenancy:
L 12 OF L X OF L 1468 GP 1 NWD PLAN B397

Licensee No. 1 (Client Last Updated: / / By Region:)
Client No: 23162
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Total Licence Demand:					
PUC	Description	Quantity/Units	From	To	Irrigated Area
01A	DOM	250.000 GD	Jan.01	Dec.31	-

Licence Comments:

POD 1:
Map No: WR 92.G.043.2.1 POD: E Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A DOM 250.000 G M Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Alderson Spring Gaz/Alias: A

POD 2:
Map No: WR 92.G.043.2.1 POD: D Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A DOM 250.000 G M Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Brown Spring Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29
TIME: 11:02
PAGE: 009

Licence Number: C025058
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT
Process Status:
Lic. Exp. Date: -
Fee Receipt No:

File Number: 0226004
Priority Date: 1959/04/03
Lic. Status Date: 1991/05/24
Proc Status Date: -
LTO Code & PID:

Appurtenancy:
L 13 OF L X OF L 1468 GP 1 NWD PLAN 8397

Licensee No. 1 (Client Last Updated: 1992/05/15 By Region: 00)

Client No: 23163
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Total Licence Demand:

PUC	Description	Quantity/Units	From	To	Irrigated Area
01A	DOM	250.000 GD	Jan.01	Dec.31	-

Licence Comments:

POD 1:

Map No: WR 92.G.043.2.1	POD: E	Rediv: N
PUC Description	Quantity/Units Qty Sto From To	Irrigated Area
01A DOM	250.000 G M Jan.01 Dec.31	-

POD Comments:
WSC: KEA Source: Alderson Spring Gaz/Alias: A

POD 2:

Map No: WR 92.G.043.2.1	POD: D	Rediv: N
PUC Description	Quantity/Units Qty Sto From To	Irrigated Area
01A DOM	250.000 G M Jan.01 Dec.31	-

POD Comments:
WSC: KEA Source: Brown Spring Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29

TIME: 11:02

PAGE: 010

Licence Number: C025059
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT
Process Status:
Lic. Exp. Date: -
Fee Receipt No:

File Number: 0226005
Priority Date: 1959/04/03
Lic. Status Date: 1991/05/24
Proc Status Date: -
LTO Code & PID:

Appurtenancy:
L 14 OF L X OF L 146B GP 1 NWD PLAN 8397

Licensee No. 1 (Client Last Updated: / / By Region:)
Client No: 23164
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Total Licence Demand:					
PUC	Description	Quantity/Units	From	To	Irrigated Area
01A	DOM	250.000 GD	Jan.01	Dec.31	-

Licence Comments:

POD 1:
Map No: WR 92.G.043.2.1
PUC Description Quantity/Units Qty Sto From To Rediv: N
01A DOM 250.000 G M Jan.01 Dec.31 Irrigated Area -
POD Comments:
WSC: KEA Source: Alderson Spring Gaz/Alias: A

POD 2:
Map No: WR 92.G.043.2.1
PUC Description Quantity/Units Qty Sto From To Rediv: N
01A DOM 250.000 G M Jan.01 Dec.31 Irrigated Area -
POD Comments:
WSC: KEA Source: Brown Spring Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29

TIME: 11:02

PAGE: 011

Licence Number: C025060 File Number: 0226006
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND Priority Date: 1959/04/03
Licence Status: C CURRENT Lic. Status Date: 1991/05/24
Process Status: Proc Status Date: -
Lic. Exp. Date: - LTO Code & PID:
Fee Receipt No:

Appurtenancy:
L 15 OF L X OF L 146B GP 1 NWD PLAN B397

Licensee No. 1 (Client Last Updated: / / By Region:)
Client No: 23165
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Total Licence Demand:
PUC Description Quantity/Units From To Irrigated Area
01A DOM 250.000 GD Jan.01 Dec.31 -

Licence Comments:

POD 1:
Map No: WR 92.G.043.2.1 POD: E Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A DOM 250.000 G M Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Alderson Spring Gaz/Alias: A

POD 2:
Map No: WR 92.G.043.2.1 POD: D Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A DOM 250.000 G M Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Brown Spring Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29
TIME: 11:02
PAGE: 012

Licence Number: C035135
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT
Process Status:
Lic. Exp. Date: -
Fee Receipt No:

File Number: 0281847
Priority Date: 1968/10/15
Lic. Status Date: 1991/05/28
Proc Status Date: -
LTO Code & PID:

Appurtenancy:
L 8 & 9 OF BLK H OF L 696 KEATS I GP 1 NWD AS SHOWN ON ATTACHED
PLAN

Licensee No 1 (Client Last Updated: / / By Region:)
Client No: 23154
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Total Licence Demand:		Quantity/Units	From	To	Irrigated Area
PUC	Description		Jan.01	Dec.31	-
01A	DOM	500.000 GD			

Licence Comments:

POD 1:
Map No: WR 92.G.033.4.3 POD: A Rediv: N
PUC Description Quantity/Units Qty Sto From To Irrigated Area
01A DOM 500.000 G T Jan.01 Dec.31 -
POD Comments:
WSC: KEA Source: Resort Spring Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29
TIME: 11:02
PAGE: 013

Licence Number: C042333
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT
Process Status:
Lic. Exp. Date: -
Fee Receipt No:

File Number: 0322057
Priority Date: 1973/10/25
Lic. Status Date: 1991/05/28
Proc Status Date: -
LTO Code & PID:

Appurtenancy:
L 1428 GP 1 NWD

Licensee No. 1 (Client Last Updated: / /

By Region:)
Client No: 23157
Work Phone: -----
Home Phone: -----
Receives Bill: Y

Permits Over Crown Land:

PCL No	Code	Description	Acres	Billed With Lic
09447	06C	OTHER - PIPELINE, ETC	0.900	Y

Total Licence Demand:

PUC	Description	Quantity/Units	From	To	Irrigated Area
01A	DOM	1,000.000 GD	Jan.01	Dec.31	-

Licence Comments:

POD 1:

Map No: WR 92.G.043.2.1

POD: K

PUC	Description	Quantity/Units	Qty	Sto	From	To	Rediv:	Irrigated Area
01A	DOM	1,000.000 G	T		Jan.01	Dec.31	-	

POD Comments:

WSC: KEA

Source: Meek Creek

Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29

TIME: 11:02

PAGE: 014

Licence Number: C042774
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT
Process Status:
Lic. Exp. Date: -
Fee Receipt No:

File Number: 0322004
Priority Date: 1973/10/17
Lic. Status Date: 1991/05/28
Proc Status Date: -
LTO Code & PID:

Appurtenancy:

L 1 OF L 1467 GP 1 NWD PLAN 6646

Licensee No. 1 (Client Last Updated: / / By Region:)

Client No: 24957

Work Phone: -----

Home Phone: -----

Receives Bill: Y

Total Licence Demand:

PUC	Description	Quantity/Units	From	To	Irrigated Area
01A	DOM	500.000 GD	Jan.01	Dec.31	-

Licence Comments:

POD 1:

Map No: WR 92.G.043.2.1

POD: H

PUC	Description	Quantity/Units	Qty	Sto	From	To	Rediv:	N
01A	DOM	500.000 G	T		Jan.01	Dec.31	-	

POD Comments:

WSC: KEA

Source: Meek Creek

Gaz/Alias: A

DATE: 1992/07/29
TIME: 11:02
PAGE: 015

Licence Number: C042775
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT
Process Status:
Lic. Exp. Date: -
Fee Receipt No:

File Number: 0322003
Priority Date: 1973/10/17
Lic. Status Date: 1991/05/28
Proc Status Date: -
LTQ Code & PID:

Appurtenancy:
IR #27 SHELTER ISLTET GP 1 NWD

Licensee No. 1 (Client Last Updated:

```

/ / By Region: )
Client No:      26476
Work Phone:     -----
Home Phone:     -----
Receives Bill: Y

```

Licensee No. 2 (Client Last Updated:

```

/ / By Region: )
Client No: 8357
Work Phone: -----
Home Phone: -----

```

Permits Over Crown Land:

PCL No	Code	Description	Acres	Billed With Lic
09579	06C	OTHER - PIPELINE, ETC	0.930	Y

Total Licence Demand:

PUC	Description	Quantity/Units	From	To	Irrigated Area
01A	DDM	500.000 GP	Jan.01	Dec.31	-

Licence Comments:

FOD 1:

Map No: WR 92.G.043.2.1

FOI: J

Rediv: N

PUC	Description	Quantity/Units	Qty	Sto	From	To	Irrigated Area
01A	DOM	500.000 G	T		Jan.01	Dec.31	-

POB Comments:

WSC: KEA

Source: Meek Creek

Gaz/Alias: A

Detailed Licence Report Water Licence Information System

DATE: 1992/07/29
TIME: 11:02
PAGE: 016

Licence Number: F019765
Dist/Prec: 29C VAN - HOWE SOUND
Region: 02 LOWER MAINLAND
Licence Status: C CURRENT
Process Status:
Lic. Exp. Date: -
Fee Receipt No:

File Number: 0225396
Priority Date: 1959/09/17
Lic. Status Date: 1991/05/28
Proc Status Date: -
LTO Code & PID:

Appurtenancy:
PARCEL B OF L 1468 KEATS I GP 1 NWD

Licensee No. 1 (Client Last Updated: 1992/06/22 By Region: 00)

Client No: 14475
Work Phone: -
Home Phone: -
Receives Bill: Y

Total Licence Demand:

PUC	Description	Quantity/Units	From	To	Irrigated Area
00B	WWK	4,000.000 GD	Jan.01	Dec.31	-

Licence Comments:

POD 1:

Map No: WR 92.6.043.2.1



PUC	Description	Quantity/Units	Qty	Sto	From	To	Rediv:	Irrigated Area
00B	WWK	4,000.000 G	T		Jan.01	Dec.31	N	-

POD Comments:

WSC: KEA

Source: Park Brook

Gaz/Alias: A



LEGEND

⑦ DENOTES WATER WELL LOCATION AND WELL NUMBER

EACH WATER WELL LOCATION ON THIS MAP REFERS TO A WATER WELL RECORD ON FILE WITH THE WATER MANAGEMENT BRANCH, MINISTRY OF ENVIRONMENT AND PARKS

CONTOUR INTERVAL m

LAND DISTRICT(S):

BRITISH COLUMBIA GEOGRAPHIC NUMBERING SYSTEM MAPPING SCALES 1:20 000 to 1:2 500


Scale: 1:5000

Metres 0 100 200 300 400 500

Feet 0 100 200 300 400 500

W.W. 92G-043-2-1

B.C.S. MAP NUMBER



LEGEND


⑦ DENOTES WATER WELL LOCATION AND WELL NUMBER


EACH WATER WELL LOCATION ON THIS MAP REFERS TO A WATER WELL RECORD ON FILE WITH THE:

WATER MANAGEMENT BRANCH
MINISTRY OF ENVIRONMENT AND PARKS

CONTOUR INTERVAL m

LAND DISTRICT(S):





LEGEND


⑦ DENOTES WATER WELL LOCATION AND WELL NUMBER

EACH WATER WELL LOCATION ON THIS MAP REFERS TO A WATER WELL RECORD ON FILE WITH THE

WATER MANAGEMENT BRANCH
MINISTRY OF ENVIRONMENT AND PARKS

CONTOUR INTERVAL m

LAND DISTRICT(S):




B.C.S. MAP NUMBER

Copies available from:
Province of British Columbia Ministry of Environment
GROUNDWATER SECTION, WATER MANAGEMENT BRANCH
Parliament Buildings, Victoria, British Columbia, V8V 1X5

SEE MAP INDEX
MAP BASE DATE: CAT-82-020
REVISION DATE:

WATER DISTRICT
PRECINCT

WATER WELL LOCATION MAP



Map No. 92G-043-2-2
To order prints quote this map number: